



# IGLC 28

BERKELEY, CA 6-12 JULY 2020

28<sup>th</sup> ANNUAL CONFERENCE OF THE  
INTERNATIONAL GROUP FOR LEAN CONSTRUCTION



# Implementation of Production System Design in House Building Projects: a Lean Journey in Chile

Karina Barth - Ph.D. Candidate

Marcus Sterzi - MSc

Carlos Formoso - PhD

Juan Ignacio Alliende - Eng

Daniela Bertín - Eng

Jorge Del Rio - Eng




# Agents involved



- Largest real estate group in Chile.
- Both development and construction.
- High degree of repetitiveness in its residential building projects.
- More than a 100 projects in progress and sells more than 3,000 units per year.
- The company is promoting a major Lean transformation process.

- Research center in the University.
- Co-Responsible for the Lean Implementation Program.



- Lean consultancy company
- Responsible for the Lean Implementation Program



- PSD translates **the production strategy into a set of decisions**, which establishes a structure to manage different activities, and **creates conditions for control and improvement** (Ballard et al. 2001a; Schramm et al. 2006).
- PSD consists of developing operation and process design in alignment with (Ballard et al. 2007):
  - product design,
  - the structure of supply chains,
  - the allocation of resources, and
  - design-for-assembly efforts.
- PSD **involves a set of interconnected decisions**, considering the need to improve the production system as a whole (Schramm et al. 2004).
- PSD can **potentialize the benefits of the LPS**, allowing the **early** identification of a larger range of problems (Frandsen et al. 2015).

# Aim of the study

- This paper reports the experience of a construction company that has implemented **PSD and the LPS over 3 years**, as part of an ongoing Lean implementation program.
- Contributions of this paper:
  - the definition of the scope and potential benefits of PSD
  - the proposition of a set of practices that can be used along the PSD stages, with emphasis on location-based planning and control

# Implementation Process and Results



## PHASE 01

Assessment of existing situation  
– 2017

### 2 PROJECTS

- Construction sites visits for assessing planning and control system:  
**Evaluation protocol**

Company did not have a systematic and explicit PSD.  
Lack of understanding of Lean concepts.  
**Large amount of WIP** (based on Batch Completeness Index and Heatmaps).



## PHASE 02

Development and initial testing  
of the Production Management  
System – 2017/18  
**3 PILOT PROJECTS**

- Training course on Lean Construction
- **Implementation of PSD** (emphasis on location-based planning and control)

**Lean Supporting Group:** consultants and company members.  
New decision category included to emphasize **layout** and **logistics planning**.  
Standardized control tools: **cycle time, takt time, WIP** and **synchronization**.



## PHASE 03


Implementation of PSD and  
LPS – 2018/19

### 5 IMPLEMENTATION PROJECTS

- Implementation of **LPS**
- Implementation of **PSD model**


Workshop organized by the LSGroup to identify and disseminate **the benefits of implementing PSD**.  
Proposition of a **PSD Guidebook**.

# PSD Company Model



# PSD Company Model: Decision Categories

## 1. Analysis and definition of construction sequence (base-unit)



## 2. Definition of resources and estimation of production capacity (base-unit)










# PSD Company Model




# PSD Company Model: Decision Categories

## 4. Definition of the execution strategy




Execution path of critical processes not included in BU: **Facades**



Work areas ("small projects") and execution path of BU processes

# PSD Company Model: Decision Categories


## 5. Layout and logistics planning





# PSD Company Model: Decision Categories

## 6. Definition of workflows (whole project)



**Line of Balance with Wagon System**

Post delivery activities

Buffer = 1 week

Buffer = 1 week


1<sup>st</sup> delivery stage

2<sup>nd</sup> delivery stage


# PSD Company Model

## 7. Identification and design of critical processes

## Workstation map for critical process



# PSD Company Model





# Benefits of Implementing PSD

- **Formalizing and making explicit planning decisions:**

Key decisions on the design of the production system were made with the participation of main stakeholders

- **Reduction in uncertainty:**

PSD helps identifying production system limitations and critical processes.





Examples of PSD meetings





# Benefits of Implementing PSD

- **Improving planning accuracy:** considering multiple alternatives of construction systems and subsystems
- **Facilitating the adoption of cycle time and takt time control:** provides information in a systematic way





# Conclusions

## Proposed PSD model X Previous studies:

- It **was tested and implemented** on several residential projects in a systematic way
- Provides more emphasis on **location-based planning and control, layout and logistics** studies during pre-construction stages
- Advances in terms of **cycle time, takt time, WIP** and **synchronization** analysis before construction
- Generates information concerning the **production system as a whole**
- Produces a set of **standardized tools** to be used to **monitor** the implementation of PSD


Data have been collected by the research team and, in the near future, the main results achieved will be systematically reported.



# IGLC 28

BERKELEY, CA 6-12 JULY 2020

28<sup>th</sup> ANNUAL CONFERENCE OF THE  
INTERNATIONAL GROUP FOR LEAN CONSTRUCTION



# THANK YOU!



Karina Barth – [karina@ldconsulting.com.br](mailto:karina@ldconsulting.com.br)

Marcus Sterzi - [marcus@ldconsulting.com.br](mailto:marcus@ldconsulting.com.br)

